GOVERNMENT OF U.P.
U.P. State Bridge Corporation Limited

INVITATION FOR BID

Bid No. : : 2732/Nauranga/20-21 **Date:** 10-11-2020

1. On behalf of Managing Director, G.M. (GKP), U.P.S.B.C. Ltd, Gorakhpur invites bids from eligible bidders registered in UPPW UPSBC and Experienced contractor having capacity of doing work of same nature under subject matters for the construction of wo detailed in the following table. The bids shall be on the Engineering, Procurement and Construction (EPC) format.

Sr. No.	Name of Project/Work(s)	Bid Security/ (Earnest Money) (Rs.)	Cost of Bid/Tender Document (Rs.)	Period of Completion
1	2	3	4	5
1.	**PRW work for the Construction of well foundation & Sub-Structure at NH-31 to Nauranga road at Shivpurghat in Distt. Ballia, U.P.** **(On P.R.W. Percentage Rate basis)**	**89,00,000.00**	**10,000.00 + 18% GST = 11,800.00**	**24 months**

Period of availability of Tender Date & Time of bid submission and Date & time of opening of Bids are as given below:

Availability of Tender for bidding		Last Date & Time for Submission of Bids	Date & Time of opening of tender	
From	To		Technical Bid	Financial Bid
12-11-2020 10.00 AM	**27-11-2020 5.00 PM**	**27-11-2020 5.00 PM**	**28-11-2020 3.00 PM**	**To be decided after evaluation of Technical Bid**

2. The complete BID document can be viewed/downloaded from official portal of etender.up.nic.in from 12-11-2020 to 27-11-2020 up 5:00 PM IST. Bid must be submitted online only at the above e-tendering portal on or before 27-11-2020 upto 5:00 PM IST. Bi received online shall be opened on 28-11-2020 at 3:00 PM IST.

   Bid through any other mode shall not be entertained. However, Bid Security, document fee, Power of Attorney and joint biddin agreement shall be submitted physically by the Bidder on or before 28-11-2020 up to 2:00 PM IST in the offices specified in tend documents. Please note that the Ministry of Road Transport & Highways reserves the right to accept or reject all or any of the BI without assigning any reason whatsoever.

3. Bids must be accompanied by Bid Security of the amount specified for the work in the above table drawn in favour of the "**U.P. Stat Bridge Corporation Limited.**" Bid Security will have to be in any one of the forms as specified in the bidding document and sha have to be valid for 45 Days beyond the validity of the bid.

4. The original **DD / Bank Guarantee** for bid security uploaded in the bid and cost of tender documents should be deposited wi the concerned **Dy. Project Manager** before the opening of the technical bid as given in the table above. The scann copies of the same should be attached in Technical Bid as prescribed in the Bidding Document, failing which the bidd shall be disqualified. If the bidder fails to deposit the original Fixed Deposit/ Bank Guarantee for bid security deposit and co of tender documents with the concerned Dy. Project Manager before the opening of the technical bid, the bidder shall b disqualified and debarred for a period of 6(six) months for submitting bids for works in the U.P. State Bridge Corporation Limited.

5. Bid documents consisting of qualification information and eligibility criterion of bidders, plans, specifications, drawing the schedule of quantities of the various classes of work to be done and the set of terms & conditions of contract to b complied with by the Contractor and scanned copies of the required documents and information as per section-2 (format & annexure) should be attached in the technical bid as prescribed in the Bidding Document.

6. The valid successful bidder has to provide the originals to the concerned authority on receipt of such letter, which will b sent through registered post.

7. The bidder has to only agree/ disagree on the conditions in the Bidding Document. The bidders who disagree on the conditions of Bidding Document cannot participate in the tender.

8. Technical bids will be opened on the day & time as specified in the above table, in the presence of the bidders who wish to attend. If the office happens to be closed on the date of receipt of the bids as specified, the bids will be received and opened on the next working day at the same time and venue.

9. Bids once submitted cannot be resubmitted or withdrawn.

10. Conditional bids and the bids not meeting the qualifying criteria on the date of receipt of bids shall be summarily rejected.

11. The undersigned has the right to accept or reject any bid and to annul the bidding process without assigning any reason.
12. All condition of T-2 will be applicable.
13. Tender should submit performance Guarantee of 5 year beyond defect liability period for structure quality and safety purpose on Rs. 100.00 Stamp after defect liability period.
14. No Price Escalation is applicable for above tender work. Hence Rate is Fixed item wise till completion of work.

10.11.20

General Manager (GKP)
U.P. State Bridge Corporation Limited
633, Shivalay, Mohaddipur,
Gorakhpur (U.P.)-273008

This is certified that I have checked the bid document and it is correct in all respects.

Dy. Project Manager
Bridge Construction Unit,
Shiv Vila GB-2,
Chandrashekhar Nagar
Ballia - 277001

Percentage BoQ

Tender Inviting Authority: General Manager, U.P. State Bridge Corporation Ltd., Gorakhpur

Name of Work:PRW work for the Construction of well foundation & Sub-Structure on NH-31 to Nauranga road at Shivpurghat for Bridge over River Ganga in Distt. Ballia, U.P.

Contract No:

Name of the Bidder/ Bidding Firm / Company :	

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	6	53	55
1	Shifting and laying of cutting edge of mild steel weighing 150 Kg/m of well foundation as per drawing and clause 1200 & 1900 of MoRT&H Specification (2001) (Cutting edge shall be supplied by the UPSBC Ltd. FOC)	37	MT	7759.00	287083.00	INR Two Lakh Eighty Seven Thousand &Eighty Three Only
2	M-35 grade Reinfoced cement concrete in well foundation excluding cost of cement as per drawings and clause 1200, 1500 & 1700 of MoRT&H Specification in well curb including Admixture as per approved mix design (cement shall be supplied by the Deptt. FOC)	1790	M^3	7050.00	12619500.00	INR One Crore Twenty Six Lakh Nineteen Thousand Five Hundred Only
	M-35 grade Reinfoced					

3	cement concrete in well foundation excluding cost of cement as per drawings and clause 1200, 1500 & 1700 of MoRT&H Specification in well steining including Admixture as per approved mix design (cement shall be supplied by the Deptt. FOC)	38560.00	M^3	6550.00	252568000.00	INR Twenty Five Crore Twenty Five Lakh Sixty Eight Thousand Only
4	M-35 grade Reinfoced cement concrete in well foundation excluding cost of cement as per drawings and clause 1200, 1500 & 1700 of MoRT&H Specification in False Steining including Admixture as per approved mix design (cement shall be supplied by the Deptt. FOC)	425	M^3	6550.00	2783750.00	INR Twenty Seven Lakh Eighty Three Thousand Seven Hundred & Fifty Only

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	6	53	55
5	M-25 grade plain cement concrete with 10 percent extra cement in well foundation excluding cost of cement as per drawings and clause 1200, 1500 & 1700 of MoRT&H Specifications in bottom plug including Admixture as per approved mix design (cement shall be supplied by the UPSBC Ltd. FOC)	4270	M^3	6350.00	27114500.00	INR Two Crore Seventy One Lakh Fourteen Thousand Five Hundred Only
6	Back filling of dredged out material in wells complete as per drawing and clause 1207 of MoRT&H Specifications.	9450	M^3	104.00	982800.00	INR Nine Lakh Eighty Two Thousand Eight Hundred Only
7	M-25 grade plain cement concrete in well foundation excluding cost of cement as per drawing and clause 1200, 1500 & 1700 of MoRT&H Specifications in intermediate plug including Admixture as per approved mix design (cement shall be supplied by the UPSBC Ltd. FOC)	145	M^3	6050.00	877250.00	INR Eight Lakh Seventy Seven Thousand Two Hundred & Fifty Only

8	M-40 grade reinforced cement concrete in well foundation excluding cost of cement as per drawings and clause 1200, 1500 & 1700 of MoRT&H Specification in well cap including Admixture as per approved mix design (Cement shall be supplied by the UPSBC Ltd. FOC)	2620	M^3	6350.00	16637000.00	INR One Crore Sixty Six Lakh Thirty Seven Thousand Only
9	Fixing and placing TMT/HYSD Bar reinforcement complete as per drawing and clause 1600 of MoRT&H specification in foundation Provision of coupler with steel bar threading above 20 mm dia. steel . No overlap shall be allowed in reinforcement in above 20mm dia steel (Steel shall be supplied by the UPSBC Ltd. FOC)	2160	MT	8050.00	17388000.00	INR One Crore Seventy Three Lakh Eighty Eight Thousand Only

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	6	53	55
10	Sinking of 8m external diameter well (other than pneumatic method of sinking) through all types of strata namely sandy soil, Clayey soil and rock as shown against each case complete as per drawings and clause 1200 of MoRT&H Specification Depth of sinking recorded from actual cutting edge level.					
10.1	For Sandy/Clayey/All type of strata Depth From G.L(Cutting edge level) to 3m Below LWL Sinking	9	M^3	8400.00	75600.00	INR Seventy Five Thousand Six Hundred Only
10.2	For Sandy/Clayey/All type of strata Depth From 3m Below LWL to 10m Below LWL Sinking	21	M^3	11100.00	233100.00	INR Two Lakh Thirty Three Thousand One Hundred Only
10.3	For Sandy/Clayey/All type of strata Depth From 10m Below LWL to 20m Below LWL Sinking	30	M^3	14900.00	447000.00	INR Four Lakh Forty Seven Thousand Only

10.4	For Sandy/Clayey/All type of strata Depth From 20m Below LWL to 30m Below LWL Sinking	30	M^3	33715.00	**1011450.00**	INR Ten Lakh Eleven Thousand Four Hundred & Fifty Only
10.5	For Sandy/Clayey/All type of strata Depth From 30m Below LWL to 40m Below LWL Sinking	30	M^3	65000.00	**1950000.00**	INR Nineteen Lakh Fifty Thousand Only
10.6	For Sandy/Clayey/All type of strata Depth From 40m Below LWL to 50m Below LWL Sinking	16	M^3	125000.00	**2000000.00**	INR Twenty Lakh Only
11	Sinking of 9.5m external diameter well (other than pneumatic method of sinking) through all types of strata namely sandy soil. Clayey soil and rock as shown against each case complete as per drawings and clause 1200 of MoRT&H Specification Depth of sinking recorded from actual cutting edge level.					
11.1	For Sandy/Clayey/All type of strata Depth From G.L(Cutting edge level) to 3m Below LWL Sinking	6	M^3	8820.00	**52920.00**	INR Fifty Two Thousand Nine Hundred & Twenty Only
11.2	For Sandy/Clayey/All type of strata Depth From 3m Below LWL to 10m Below LWL Sinking	14	M^3	11655.00	**163170.00**	INR One Lakh Sixty Three Thousand One Hundred & Seventy Only

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	**Item Description**	**Quantity**	**Units**	**Estimated Rate in Rs. P**	**TOTAL AMOUNT Without Taxes in Rs. P**	**TOTAL AMOUNT In Words**
1	2	4	5	6	53	55
11.3	For Sandy/Clayey/All type of strata Depth From 10m Below LWL to 20m Below LWL Sinking	20	M^3	15645.00	**312900.00**	INR Three Lakh Twelve Thousand Nine Hundred Only
11.4	For Sandy/Clayey/All type of strata Depth From 20m Below LWL to 30m Below LWL Sinking	20	M^3	35400.00	**708000.00**	INR Seven Lakh Eight Thousand Only
11.5	For Sandy/Clayey/All type of strata Depth From 30m Below LWL to 40m Below LWL Sinking	20	M^3	68250.00	**1365000.00**	INR Thirteen Lakh Sixty Five Thousand Only
11.6	For Sandy/Clayey/All type of strata Depth From 40m Below LWL to 50m Below LWL Sinking	20	M^3	131250.00	**2625000.00**	INR Twenty Six Lakh Twenty Five Thousand Only
11.7	For Sandy/Clayey/All type of strata Depth From 50m Below & above	3	M^3	131250.00	**393750.00**	INR Three Lakh Ninety Three Thousand Seven Hundred & Fifty Only
	Sinking of 10m external diameter well (other than					

12	pneumatic method of sinking) through all types of strata namely sandy soil. Clayey soil and rock as shown against each case complete as per drawings and clause 1200 of MoRT&H Specification Depth of sinking recorded from actual cutting edge level.					
12.1	For Sandy/Clayey/All type of strata Depth From G.L(Cutting edge level) to 3m Below LWL Sinking	42	M^3	9660.00	**405720.00**	INR Four Lakh Five Thousand Seven Hundred & Twenty Only
12.2	For Sandy/Clayey/All type of strata Depth From 3m Below LWL to 10m Below LWL Sinking	98	M^3	12765.00	**1250970.00**	INR Twelve Lakh Fifty Thousanc Nine Hundred & Seventy Only
12.3	For Sandy/Clayey/All type of strata Depth From 10m Below LWL to 20m Below LWL Sinking	140	M^3	17135.00	**2398900.00**	INR Twenty Three Lakh Ninety Eight Thousand Nine Hundred Only
12.4	For Sandy/Clayey/All type of strata Depth From 20m Below LWL to 30m Below LWL Sinking	140	M^3	38772.00	**5428080.00**	INR Fifty Four Lakh Twenty Eigh Thousand &Eighty Only
12.5	For Sandy/Clayey/All type of strata Depth From 30m Below LWL to 40m Below LWL Sinking	140	M^3	74750.00	**10465000.00**	INR One Crore Four Lakh Sixty Five Thousand Only
12.6	For Sandy/Clayey/All type of strata Depth From 40m Below LWL to 50m Below LWL Sinking	115	M^3	143750.00	**16531250.00**	INR One Crore Sixty Five Lakh Thirty One Thousand Two Hundred & Fifty Only

NUMBER #	**TEXT #**	**NUMBER #**	**TEXT #**	**NUMBER**	**NUMBER #**	**TEXT #**
Sl. No.	**Item Description**	**Quantity**	**Units**	**Estimated Rate in Rs. P**	**TOTAL AMOUNT Without Taxes in Rs. P**	**TOTAL AMOUNT In Words**
1	**2**	**4**	**5**	**6**	**53**	**55**
12.7	For Sandy/Clayey/All type of strata Depth From 50m Below & above	13	M^3	143750.00	**1868750.00**	INR Eighteen Lakh Sixty Eight Thousand Seven Hundred & Fift Only
13	M-35 Reinforcement Cement concrete in Sub-structure complete as per drawing and technical specification such as pier(Plate type) including Admixture as per approved mix design (cement shall be supplied by the Deptt. FOC)	5180	M^3	7125.00	**36907500.00**	INR Three Crore Sixty Nine Lakl Seven Thousand Five Hundred Only
	M-35 Reinforcement Cement concrete in Sub-					

14	structure complete as per drawing and technical specification such as pier cap including Admixture as per approved mix design (cement shall be supplied by the Deptt. FOC)	130	M^3	7125.00	926250.00	INR Nine Lakh Twenty Six Thousand Two Hundred & Fifty Only
15	M-35 Reinforcement Cement concrete in Sub-structure complete as per drawing and technical specification such as Abutment wall including Admixture as per approved mix design (cement shall be supplied by the Deptt. FOC)	500	M^3	7125.00	3562500.00	INR Thirty Five Lakh Sixty Two Thousand Five Hundred Only
16	M-45 Reinforcement Cement concrete in Sub-structure complete as per drawing and technical specification such as Bearing Padestal including Admixture as per approved mix design (cement shall be supplied by the Deptt. FOC)	11	M^3	7125.00	78375.00	INR Seventy Eight Thousand Three Hundred & Seventy Five Only
19	Fixing and placing TMT/HYSD Bar reinforcement complete as per drawing and clause 1600 & 2200 of MoRT&H specification in Sub-Structure Provision of coupler with steel for threading above 20 mm dia. Steel . No overlap shall be allowed in reinforcement in above 20mm dia steel (Steel shall be supplied by the UPSBC Ltd. FOC)	1460	MT	8100.00	11826000.00	INR One Crore Eighteen Lakh Twenty Six Thousand Only

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	6	53	55
20	Construction and Dismentaling of Steel Pile Bridge complete in all respect as per requirement. Vibro, Generator, Pile material & RSJ Girder, Angle bracing & chequred plate shall be provided by department excluding POL.	400	RM	12500.00	5000000.00	INR Fifty Lakh Only

21	Constructing Temporary Sheet Pile Island for construction of well foundation of 8.0m & 10.0m outer dia well complete in all respect including sheet pile fixing, placing & removing at desired safe place. As per requirement Vibro, Generator & Sheet Pile shall be provided by department excluding POL.(for more than 4.0m depth of water)	500	MT	8000.00	**4000000.00**	INR Forty Lakh Only
22	Making of Service Road for work in river (Avg. Depths of water 1.00 meter)	200	RM	3000.00	**600000.00**	INR Six Lakh Only
Total in Figures					443845068.00	INR Forty Four Crore Thirty Eigt Lakh Forty Five Thousand &Six Eight Only
Quoted Rate in Figures			**Select**		0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only				